

# Foosball Installation Instructions

Unload all items using proper equipment.

Required for offloading: Forklift or other lifting device such as backhoe or tractor with forks. Please follow manufacturers lift and distance weight ratings. Foosball pallet weighs 1550 pounds.

## Tools:

1 1/8" socket  
Hex drivers  
Hand Truck (dolly)  
4' level  
Electric screwdriver for shipping pallet  
Phillips bits for packaging  
Two 12' lifting straps  
Lifting hook or shackle

## Instructions:

1. Start the bolts that hold the legs together using 2x2 powder coated runners and bolts provided. Square the legs measuring diagonally from the ends of the slotted holes in the runners, Then tighten the bolts.
2. We recommend installing on a level surface, most concrete slabs are sloped for drainage in that case we suggest a permanent shim like granite tile under the legs to get them level and once install is complete suggest sacking the area under the foot of the leg with mortar.
3. Bolt down to concrete using supplied brackets and hardware.
4. Lift concrete Foosball table by cradling the concrete in two 12' lifting straps. DO NOT ATTEMPT TO LIFT USING FOOSBALL RODS. Damage to the table and weight shifting may occur.
5. Bolt up through powder coated runners into foosball table.

